

नेपाल सरकार
कृषि तथा पशुपन्छी विकास मन्त्रालय
प्रधानमन्त्री कृषि आधुनिकीकरण परियोजना
परियोजना कार्यान्वयन इकाई, कास्की

BILL OF QUANTITY (BOQ) of Nursery Tunnel

क्र.सं.	काम/सेवाको विवरण	एकाइ (Unit)	परिमाण (Qty)	Rate per unit (दर)		जम्मा लगत (Total)	Remarks
	आइटम			In Figure	In words		
1	Site clearance works before and after construction	Job	1				
2	E/W Excavation in foundation in soft soil including lift 1.5 m and lead up to 10m all complete	cum	2.11				
3	Providing and laying P.C.C. 1:2:4 including curing all complete	cum	0.67				
4	Providing and laying of stone masonry wall of 1:6 c/s mortar all complete	cum	3.17				
5	Filling of mud inside nursery tunnel 20cm height from ground level all complete	cum	14.40				
6	Supply & fixing of MS pipes for truss with necessary cutting,welding,painting & fixing all complete as per instruction of site incharge	kg	452.20				
7	Providing of 5 layer 200 micron UV stabalized plastic sheet for roofing work with necessary fittings all complete as per instruction of site incharge.	Sqm	220				
8	Providing of UV stabalized White Anti Insect net of mesh size 40, not less than 70 GSM all complete as per instruction of site incharge	Sqm	108				
9	Supply and fixing of alumunium profile with PVC/GI coated zigzag spring all complete as per instruction of site incharge.	Rm	90mtr or as per requirement				
10	Supply and Fixing of Roller Gear handle small with 1.5" dia.MS pipe 1.8mm thick in both sides for rolling plastic all complete	Set	2				
11	Providing and laying 500 ltr PVC extra heavy water tank with Inlet, outlet, over flow, cleanout hole etc. all complete as per instruction of site incharge	Set	1				
12	Supply & fixing of tank stand for 500 litre water tank with ms square pipe of 1.5" dia. 2mm thick main post and main bearer with ms square pipe of 1.5" dia. 2mm thick girt with necessary cutting,welding,painting & fixing all complete as per instruction of site incharge	Kg	34.194				
13	Providing of 0.5 HP surface electric pump with suitable inlet and outlet all complete	Set	1				
14	UV stabalized Shade Net with 50% shading capacity with weight not less than 70 GSM, Green in colour, preferred if UV protected with complete installation	Sqm	72 or as per requirement				
Total Estimated Cost							
13% Vat for vatable item							
Grand Total							

तयार गर्ने:
हस्ताक्षर:
नाम:
पद:
मिति:

स्वीकृत गर्ने :
हस्ताक्षर:
नाम:
पद:
मिति:

